


- LEGEND**
- A = A/C
 - ASPH = Asphalt
 - BM = Bench Mark
 - BRG = Bearing
 - CB = Catch basin
 - CBS = Concrete Block Structure
 - CH = Chord
 - Chatta = Chattahoochee
 - C = Center Line
 - CLF = Chain Link Fence
 - CL = Clear
 - CONC. = Concrete
 - D = Delta
 - Ø = Diameter
 - DH = Drill Hole
 - DME = Drainage & Maintenance Easement
 - E.B. = Electric Box
 - Enc. = Encroachment
 - F.F. = Finish Floor
 - F.H. = Fire Hydrant
 - F.I.R. = Found Iron Rebar
 - FPL = Florida Power & Light
 - F.I.P. = Found Iron Pipe
 - FD. = Found
 - L.P. = Light Pole
 - M. = Measured
 - M.F. = Metal Fence
 - M.H. = Manhole
 - M = Monument Line
 - MON. = Monument
 - N/A = Not Applicable
 - ND = Nail & Disc
 - NTS = Not to Scale
 - O/S = Offset
 - O.U.L. = Overhead Utility Lines
 - OH = Overhang
 - P = Plat
 - PB = Plat Book
 - PC = Point of Curvature
 - PCP = Permanent Control Point
 - PG = Page
 - P.I. = Point of Intersection
 - PL = Property Line
 - PL = Planter
 - P.O.B. = Point of Beginning
 - P.O.C. = Point of Commencement
 - P.P. = Power Pole
 - P.R.M. = Permanent Reference Monument
 - P.R.C. = Point of Reverse Curvature
 - PT = Point of Tangency
 - R = Radius
 - R/R = Railroad
 - PSM = Professional Surveyor Mapper
 - R/W = Right-of-Way
 - SWK = Sidewalk
 - Sec. = Section
 - (TYP) = Typical
 - T = Tangent
 - U.E. = Utility Easement
 - W.F. = Wood Fence
 - W.M. = Water Meter
 - W.V. = Water Valve
 - ± = Denotes Spot Elevations Taken

(1) All made shown herein are public unless otherwise noted.
 (2) No identification card found on property unless otherwise noted.
 (3) Distance along boundary are recorded and measured unless otherwise noted.
 (4) The graphic portions of this document are intended to be displayed at the graphic scale as shown on the title sheet. Reproductions and as such, should be considered when obtaining scaled data.
 (5) Accuracy: The expected use of land as classified in the Standards of Practice (SIP-FAC), is "Suburban". The minimum relative distance accuracy for this type of boundary survey is 1 foot in 1000 feet. The minimum measurement and calculation of a closed geometric figure was found to exceed this requirement.
 (6) Contact the appropriate authorities prior to any design work or excavation on the herein described parcel for building, zoning information and utilities location.

NOTE: a) All encroachments and/or encroachments shown herein are of the apparent nature, hence legal ownership is not shown. b) The issue of this survey is only for the exclusive and specific use of those persons, parties or institutions in the certification. c) Under no circumstances shall the surveyor be held liable for any errors or omissions in the survey. d) The information shown herein does not imply that the subject property will or will not be free from flooding or damage and does not create liability on the part of the firm or employee thereof, for any such damage or loss. e) Land depicted herein were surveyed per legal description provided by client and no claims as to ownership or matters of title are made or implied.



This property described as:

PARCEL 1:
 That part of Lots 4, 5, 6, 9, 10 and 11, and that part of a 20-foot strip of land formerly an alley lying immediately South of Lots 9, 10 and 11, of Block 54, of FISHER'S FIRST SUBDIVISION OF ALTON BEACH, according to the Plat thereof, as recorded in Plat Book 2, Page 77, of the Public Records of Miami-Dade County, Florida, more particularly described as follows:
 Beginning at a point on the Southerly line of Lincoln Road at a distance of 40 feet Westerly from the Northeast corner of Lot 9 aforesaid (the Northerly line of Lot 9 and the Southerly line of Lincoln Road being identical); thence (1) run Westerly along the Southerly line of Lincoln Road a distance of 30 feet to a point; thence (2) run Southerly, parallel with the dividing line between Lots 9 and 10, of Block 54 aforesaid, 100 feet to a point; thence (3) run Westerly and parallel with the Southerly line of Lincoln Road a distance of 35 feet, more or less, to a point, which point is a distance of 5 feet Westerly from the dividing line of Lots 10 and 11, of Block 54 aforesaid; thence (4) run Southerly, along a line parallel with and 5 feet Westerly from the dividing line between Lots 10 and 11 and the extension thereof Southerly, a distance of 196.8 feet, more or less, to the Southerly line of the North 1/2 of Lot 4, Block 54 aforesaid; thence (5) run Easterly, along the Southerly line of the North 1/2 of the said Lot 4, a distance of 100 feet, more or less, to a point, said point being 5 feet Westerly from the dividing line between Lots 8 and 9, Block 54, extended Southerly; thence (6) run Northerly, along a line parallel with and 5 feet Westerly from the dividing line between the said Lots 8 and 9 (as extended Southerly), a distance of 196.8 feet, more or less, to a point 100 feet distant from the Southerly line of Lincoln Road; thence (7) run Westerly, parallel with the Southerly line of Lincoln Road, a distance of 35 feet to a point; thence (8) run Northerly, parallel with the dividing line between Lots 9 and 10 aforesaid, 100 feet to the place of beginning.

PARCEL 2:
 TOGETHER WITH a non-exclusive easement granted pursuant to Easement Right over Private Road recorded in Deed Book 2600, Page 459, as affected by Declaration as to Permanent Easements recorded in Deed Book 3622, Page 49, both of the Public Records of Miami-Dade County, Florida, being more particularly described as follows:

That part of the South 20 feet of the North 1/2 of Lot 4, Block 54, of FISHER'S FIRST SUBDIVISION OF ALTON BEACH, according to the Plat thereof, recorded in Plat Book 2, Page 77, of the Public Records of Miami-Dade County, Florida, lying East of the dividing line between Lots 8 and 9, of said Block 54, as extended Southerly to a point where it intersects the Southerly line of the North 1/2 of said Lot 4.

PARCEL 3:
 TOGETHER WITH a non-exclusive 5 foot easement over the South 20 feet of the North 1/2 of Lot 4, Block 54, of FISHER'S FIRST SUBDIVISION OF ALTON BEACH, according to the Plat thereof, recorded in Plat Book 2, Page 77, of the Public Records of Miami-Dade County, Florida, granted in that certain Warranty Deed recorded in Official Records Book 9933, Page 976, of the Public Records of Miami-Dade County, Florida; which said 5 foot strip of land is bounded on the East by the extension Southerly of the boundary line between Lots 8 and 9, of said Block 54, to a point where it intersects the Southerly line of the North 1/2 of said Lot 4; on the South by the Southerly line of the North 1/2 of said Lot 4; on the West by the East line of the land described as Parcel 1 herein; and on the North by the North line of the South 20 feet of the North 1/2 of said Lot 4.

230 Lincoln Road, Miami Beach, FL 33139

CERTIFY TO:

- Camford Corp
- C/O S Karam
- Carib Mall Associates LLC

"THIS SURVEY DECLARATION IS MADE ON THE FIELD DATE INDICATED, TO THE OWNER(S) LISTED. IT IS NOT TRANSFERABLE TO ADDITIONAL INSTITUTIONS OR SUBSEQUENT OWNERS."

Bearing, if any, shown based on Plat Meridian (reference) NORTH ± N88°05'19"E

REVISIONS: 04/06/16 Survey Update, <i>JA</i>	FLOOD ZONE AE	COMM. No. 1206651	PANEL NO. 0317	SUFFIX: L	Not valid unless it bears the signature and the original raised seal of Florida licensed Surveyor and Mapper.
	F.I.R.M.DATE 09/11/09	F.I.R.M.INDEX 09/11/09	BASE ELEV. +8FT	N.G.V.D.	

BOUNDARY SURVEY.
 I HEREBY CERTIFY: that this survey meets the Standards of Practice as set forth by the FLORIDA BOARD OF PROFESSIONAL SURVEYORS AND MAPPERS in Chapter 5J-1, Florida Administrative Code, pursuant to Section 472.027 Florida Statutes.
René Aiguesvives
 RENE AIGUESVIVES 05/04/15
 PROFESSIONAL SURVEYOR AND MAPPER No. 4327, State of Florida.

Alvarez, Aiguesvives and Associates, Inc.
 Surveyors, Mappers and Land Planners
 5701 S.W. 107th Avenue #204, Miami, FL 33137
 Phone 305.220.2424 Fax 305.552.8181
 L.B. No. 6867 / E-mail: aaasurvey@aol.com

Field Date 04/29/15	Scale: 1"=30'	Drawn by: R.S.	Drwg. No. 14-17163
------------------------	------------------	-------------------	-----------------------

HPB SIGNAGE SUBMITTAL 12/27/2016