



ABBR.	QTY.	BOTANICAL NAME	COMMON NAME	SPECIFICATIONS	NATIVE (YES/NO)
TREES					
Bla	5	<i>Bursera arborea</i>	Verawood	4" DBH, 18' H.	NO
Bli	1	<i>Bursera simaruba</i>	Gumbo Limbo	4" DBH, 18' H.	YES
Pr	6	<i>Prunera racemosa</i>	Star Plum	4" DBH, 18' H.	YES
Ca	3	<i>Conocarpus Erectus</i>	Green Buttonwood	4" DBH, 18' H.	YES
Tra	1	<i>Thrinax cadida</i>	Florida Thatch Palm	45 Gal.	YES
Cca	1	<i>Chamaedorea cataractarum</i>	Cat Palm	25 Gal.	NO
Lai	1	<i>Legastocnema indica</i>	Crape Myrtle	3" DBH, 15' H.	NO
Mf	7	<i>Mycocarpus fragrans</i>	Simpson Stopper	12" Ht. 6" Sp. Full to base	NO
Co	6	<i>Conocarpus erectus var. strictus</i>	Silver Buttonwood	12" Ht. 6" Sp. Full to base	NO
Elo	1	<i>Eugenia florida</i>	Spanish Stopper	12" Ht. 6" Sp. Full to base	NO
Cl	2	<i>Syzygium lucida</i>	Scarvesee	12" Ht. 6" Sp. Full to base	NO
Shrubs					
Cs	55	<i>Chrysobalanus icaco</i>	Redtip Cocoplum	7 Gal.	YES
Cs	28	<i>Conocarpus erectus var. strictus</i>	Silver Buttonwood	15 Gal.	YES
Ch	21	<i>Chrysobalanus icaco</i>	Horizontal Cocoplum	7 Gal.	YES
Gg	5	<i>Galphimia glauca</i>	Thrifts, Rain-Of-Gold	7 Gal.	YES
Pl	17	<i>Psychotria ligustrifolia</i>	Bahama Coffee	7 Gal.	YES
Cm	50	<i>Cissua rosea Nyana</i>	Dwarf Fritill Apple	7 Gal.	YES
Ph	1	<i>Phyllanthus coccinchiensis</i>	Catching Phyllanthus	3 Gal.	NO
Gr	250	<i>Liriope muscari</i>	Lilyart	3 Gal.	YES
Mn	12	<i>Macrocarum scolopendrium</i>	Wart Fern	3 Gal.	NO
Accents					
Md	12	<i>Monstera deliciosa</i>	Mexican Breadfruit	7 Gal.	YES
Al	9	<i>Alcantara imperialis</i>	Same	7 Gal.	NO
Supplemental					
TBD			Site Bark Mulch (for planting beds)	T.B.D. by Landscape Contractor	
TBD			Planting Topsoil	T.B.D. by Landscape Contractor	
TBD			Fertilizer (initial plant establishment)	T.B.D. by Landscape Contractor	

TREES TO BE REMOVED		
#	BOTANICAL NAME	COMMON NAME
15	<i>Dicotylesperma album</i>	Hurricane Palm
33	<i>Persea americana</i>	Avocado Tree
34	<i>Morinda citrifolia</i>	Noni Tree
35	<i>Phoenix canariensis</i>	Canary Island Date Palm
TOTAL AMOUNT OF DBH TO BE REMOVED		69"
NUMBER OF PALMS TO BE REMOVED		1

MITIGATION CALCULATION	
Total Number of Replacement Trees Provided	11
Number of trees with 4" DBH & 18' HT.	



